


SECTION

- ①. 1 FT. MINIMUM - 2 FT. MAXIMUM, LOCATED IN P.U.E.
- ②. UTILITY BOX WITH COVER, TO BE LOCATED CLEAR OF DRIVEWAYS (SEE APPROVED MATERIALS LIST)
- ③. FINISHED GRADE
- ④. POLYETHYLENE TUBING, PE3408, 200 PSI, SDR9, BLUE (SEE APPROVED MATERIAL LIST)
- ⑤. STRAIGHT CURB STOP (SEE APPROVED MATERIAL LIST)
- ⑥. L.C.U. APPROVED DUAL CHECK BACKFLOW PREVENTER (SEE APPROVED MATERIAL LIST)
- ⑦. WATER METER BOX (LCU OWNED & MAINTAINED)
- ⑧. END OF LCU MAINTENANCE AT METER

NOTES:

1. INITIAL DEVICE TESTING REQUIRED. REFURBISH OR REPLACE DUAL CHECK BACKFLOW PREVENTER AT LEAST EVERY 5 TO 10 YEARS.
2. FOR SINGLE FAMILY RESIDENTIAL USE (ONLY)

NOT TO SCALE

		LEE COUNTY UTILITIES ENGINEERING <small>1500 MONROE STREET FORT MYERS, FLORIDA 33901</small>
TITLE: 5/8" THROUGH 2" CROSS CONTROL ASSEMBLY (RESIDENTIAL)		
REVISION: 12/18/24	DETAIL NO: W-07.dwg	